

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 25 1963
 2-25-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. E d Walker guarantees payment of the plugging fee.Operator's full Name: Petroleum Inc.Complete Address: 352 North Broadway, Wichita, KansasLease Name: Dauner Well No. # 1Location: NW NE SW Sec. 36 Twp. 30S Rge. 8 (E) (W) WCounty Kingman Total Depth 4485 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Walker was instructed to plug the well as follows:253' of 85/8" surface pipe circulated with cement.Fill hole with heavy mud to 180', 1/2 sack of hulls, 1st
cementing plug, cement with 20 sacks. Fill hole withheavy mud to 40', 1/2 sack of hulls, 2nd cementing plug.cement with 10 sacks to base cellar. Rat hole bridged
and cemented with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent