

State of Kansas



15.167.30281.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Leo J. Dreiling Oil Co. has this
date requested permission to plug the following described well:

Mr. Leo J. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name: Barell Well No. # 9

Location: SW NE NE Sec. 32 Twp. 15 Rge. 11 (E)(W) W

County Russell Total Depth 3340 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bob Miller was instructed to plug the well as follows:
8 5/8" 158' Cwc.

Circulated hole with heavy mud to 300', set plug, & displaced 20 sax
cement thru drill pipe. Mud to 150', set plug with 1/4 sax hulls, &
displaced 20 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls,
plug, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don L. ...
Conservation Division Agent