



JOHN CARLIN, Governor
R. C. LOUX, Chairman
JANE T. ROY, Commissioner
PHILLIP R. DICK, Commissioner
CAROL J. LARSON, Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

September 2, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Clements of Leben Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Big J Production Co., Inc. & Quadel Energy

Complete Address: 427 N. St. Francis, Wichita, Kansas 67202

Lease Name: Cornwell Well No. 1

Location: NW NE Sec. 3 Twp. 24 Rge. 15 (E) (W)

County: Stafford Total Depth: 4204'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Clements was instructed to plug the well as follows:

8-5/8"-300'-circ. Top Anhydrite 945' Circulate hole and fill with mud.

Pump 60 sacks cement through drill pipe at 600'. Pump 40 sacks cement

through drill pipe at 310'. Fill hole with mud to 40'. Push plug and

1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rathole

with 10 sacks cement. Cement Mousehole with 10 sacks cement

Very truly yours,

Walter J. Norman
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

SEP - 6 1981
CONSERVATION DIVISION
Wichita, Kansas

9-9-81