

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 28 1964

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Sunray DX Oil Company has this
 date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Company

Complete Address: 321 West Douglas. Wichita, Kansas

Lease Name: Rohlman Well No. 1

Location: SW NW Sec. 9 Twp. 24 Rge. (E) (W) 40

County Hamilton Total Depth 2405' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

8 5/8"-140' Circulated w/cement. 4 1/2"-2404' Cemented.

Plug back bottom w/cement 2405' to 2399' Perforations 2393' to 2390'

Plug bottom w/5 Sax.cement 2399' to 2339' Mud 2339' to 600'

25 Sax.cement 600' to 525' Mud 525' to 140'

25 Sax.cement 140' to 65' Mud 65' to 50'

Rock bridge 50' to 40' 15 Sax.cement 40' to 0

Hugh Ross
 Conservation Division Agent