

WELL PLUGGING RECORD

Russell County, Sec. 10 Twp. 15 Rge. ~~14~~ 14 (W)

Location as "NE/CNW/SW" or footage from lines C N/2 NE SE

Lease Owner NATIONAL COOPERATIVE REFINERY ASSOCIATION

Lease Name Boxberger "B"

Well No. 7

Office Address P. O. Box 6, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Input Well

Date well completed March 30, 1955

Application for plugging filed February 1, 1972

Application for plugging approved February 8, 1972

Plugging commenced February 29, 1972

Plugging completed February 29, 1972

Reason for abandonment of well or producing formation No longer needed as an injection well.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan

Producing formation Lansing Depth to top 2953 Bottom 3198 Total Depth of Well 3218' Feet PBTB 3185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	754'	None
				5 1/2"	3212'	1,609.55'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Move in. Rig up. Shot @ 2540', 3280', 2191', 1996', 1793' & 1600'. Pull 1,609.55' - 5 1/2" csg. Sand back from 3185' to 2950'. Dump 5 sxs. cem. Dump Rock Bridge to 400' & 8 1/2 yds. Ready-Mix to surface. Complete @ 11:40 AM, 2-29-72. P. D. Shobe, Company Representative.

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Comstock Pipe Pulling, Inc.
Address 320 North Park, Stafford, Kansas 67578

STATE OF Kansas, COUNTY OF Barton, ss.
I. J. Gotsche

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

I. J. Gotsche, District Superintendent
P. O. Box 6, Great Bend, Kansas 67530
(Address)

WITNESSED and SUBSCRIBED to before me this 3 rd day of March, 1972

Russell E. Turnbow

Notary Public.

My commission expires April 14, 1975


Company. NATIONAL COOPERATIVE REFINERY ASSOCIATION
 Farm. Boxberger "B" No. 7

SEC. 10 T. 15 R. 14W
 CN/2 NE SE

Total Depth. 3221'
 Comm. 3-7-55
 Shot or Treated.
 Contractor.
 Issued. 5-14-55

Comp. 3-20-55

County Russell
 KANSAS



CASING:

10 3/4" 754' cem w/400 sx
 5 1/2" 3212' cem w/75 sx

Elevation. 1745' DF

Production. 36 BO & 28 BW

Figures indicate Bottom of Formations

shale	160
red rock	200
shale & shells	350
sand	400
red rock	748
anhydrite	780
shale & shells	1230
salt	1415
shale & shells	1560
lime & shale	2015
shale & shells	2595
lime & shale	2889
Heebner	2893
lime & shale	2953
Lansing	2955
lime	3210
Arbuckle	3221
Total Depth	

Tops: Scout	
Topeka	2660
Heebner	2889
Toronto	2907
Lansing	2953
Conglomerate	3198
Arbuckle	3210

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 7 1972
 CONSERVATION DIVISION
 Wichita, Kansas