


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

RUSSELL County. Sec. 10 Twp. 15 Rge. (E)14 (W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner RUDY HERMAN OIL OPERATIONS
Lease Name BOXBERGER Well No. 3
Office Address BOX 562, GREAT BEND, KANSAS 67530
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed MARCH 23 1955
Application for plugging filed APRIL 7 1966
Application for plugging approved 19
Plugging commenced MAY 7 1966
Plugging completed MAY 12 1966
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN
Producing formation Depth to top Bottom Total Depth of Well 3221 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	770'	NONE
				5 1/2"	3221'	2010.54'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PBTD 2465'
2465' - 2300' - SAND
2300' - 2260' - 5 SACKS CEMENT
2260' - 300' - MUD
300' - 290' - ROCK BRIDGE
290' - BASE - 4 YARDS READY MIX CEMENT

RECEIVED
STATE CORPORATION COMMISSION

JUN - 3 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. Nutt (employee of owner) or (~~OWNER~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
BOX 562, GREAT BEND, KANSAS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 2ND day of JUNE, 19 66

My commission expires JULY 31, 1966
Mary M. Guesnie
Notary Public.

15-167-03512-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- RUDY HERMAN
Farm- Boxberger No. 3

SEC. 10 T. 15 R. 14W
SE SE NW

Total Depth. 3241'
Comm. 3-12-55 Comp. 3-23-55
Shot or Treated.
Contractor.
Issued. 8-30-58

County Russell
KANSAS



CASING:
8" 770'
5 1/2" 3321'

Elevation. 1766' DF

Production. 15 BOPD

Figures Indicate Bottom of Formations.

DRILLERS LOG NOT AVAILABLE

1st sand Tarkio
sand 2348-50 no show

2nd sand
2361-65, poor saturated, no
odor, slight show free oil.

3rd sand
2436-37, 2445-49, show free oil

Topeka
2843-45, lime no porosity
2854-58, lime, no odor

Dodge
2923-36, lime trace free oil

DST #1 2906-30, rec. 10' mud.

Douglas
2953-56, shale fine, no odor, slight show
free oil

Lansing-Kansas City
2965-69, lime trace, poor porosity
2987-89, faint odor, show free oil

DST #2 2966-93, op 1 hr, rec. 240' free gas
in drill pipe.

Arbuckle
3219-23, spotted stain, faint odor, slight
show free oil

Total Depth 3241

TOPS:
Anhydrite 767
Grandhaven 2333
Tarkio 1st 2348
Tarkio 2nd 2361
Tarkio lime 2401
Tarkio Sand 3rd 2436
Heebner 2901
Dodge 2919
Lansing-Kansas City 2963
Base Kansas City 3168
Arbuckle 3219

RECEIVED
STATE CORPORATION COMMISSION

JUN - 3 1966

PRESERVATION DIVISION
Wichita, Kansas