

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-167-03517-0000

LEASE NAME Boxberger A-6

WELL NUMBER _____

SPOT LOCATION SE NE SW

SEC. 10 TWP. 15s RGE. 14w (E) or (W)

COUNTY Russell

Date Well Completed _____

Plugging Commenced 11/25/85

Plugging Completed 12/3/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS Box 1404, McPherson, Ks. 67460

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3228'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	775'	none
				5 1/2"	3216'	2025'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 2800' & 5 sacks cement. Shot pipe at 2521' & 2025'
Pulled 63 joints of pipe. Plugged well with 5 hulls, 8 5/8 plug, & 200 sacks
cement.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of December, 1985

My Commission expires:



RECEIVED Notary Public
STATE CORPORATION COMMISSION

12-12-85
DEC 12 1985

Form CP-4
Revised 01-84


15-167-03517-0000

K. G. S. LIBRARY
KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
FOR EASTERN ROCK - WICHITA, KANSAS
COMPANY NATIONAL COOPERATIVE REFINERY ASSOCIATION

FARM Boxberger "A" NO. 6.

SEC. 10 T. 15 S. 11W
Loc. Approx. SE NE SW
330' N of SL, 2590' E of NW

TOTAL DEPTH 3228
COMM. 9-13-50 COMP. 9-25-50
SHOT OR TREATED
CONTRACTOR Armer Drlg Co., Inc.
ISSUED 12-16-50



CASING
8 5/8" 775' cem w./375 sx.
5" 3216' cem w /125 sx.

ELEVATION 1772 KB
PRODUCTION Prop 114 bbls / MW

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	130
shale, shells	180
shale, shells, iron	300
shale, shells	425
sand, shale	465
shale, red bed	645
shale, shells	764
gyp, shells	771
anhydrite	814
red bed, shale	880
shale, shells	1410
lime, shale	1615
salt, shale	1665
lime, shale	2000
shale, shells	2300
lime, shells	2320
shale, shells	2728
lime, shale	2910
lime	3173
lime, shale	3194
lime	3218
lime	3228
Total Depth	

Tops:

Heebner	2906
Lansing-Kansas City	2966
Arbuckle	3215

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1985

CONSERVATION DIVISION
Wichita, Kansas