


Give All Information Completely  
Make Required At Navit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Russell County. Sec. 10 Twp. 15 Rge. 14W (E) (W)  
Location as "NE/CNW/SW" or footage from lines 1250' S of N Line, 75' W of E line,  
Lease Owner Bennett & Roberts Drilling Co. NE/4  
Lease Name Flegler Well No. 1  
Office Address Russell, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 9/13 19 55  
Application for plugging filed 10/6 19 55  
Application for plugging approved 10/7 19 55  
Plugging commenced 10/11 19 55  
Plugging completed 10/13 19 55  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3225 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN    | PULLED OUT |
|-----------|---------|------|----|--------|-----------|------------|
|           |         |      |    | 8 5/8" | 660'      | None       |
|           |         |      |    | 5 1/2" | 3209 1/2' | 2120'      |
|           |         |      |    |        |           |            |
|           |         |      |    |        |           |            |
|           |         |      |    |        |           |            |
|           |         |      |    |        |           |            |
|           |         |      |    |        |           |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with crushed rock from 2332' to 2310'. Dumped 5 sax cement at 2310' with dump bailer. Top of cement, 2280'. Filled hole with mud to 300', set rock bridge, dumped 20 sax cement. Top of cement, 240'. Filled with mud to 35', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Miller Casing Pulling Co.  
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
Harold Wurst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst  
Russell, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 55

My commission expires 6/17/58

Clara Hummel  
Notary Public.

**PLUGGING**  
FILE SEC-10-T-15R-140  
BOOK PAGE 6 LINE 39

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 19 1955  
CONSERVATION DIVISION  
Wichita, Kansas

10-19-55

Bennett & Roberts Drilling, Inc.  
Flegler #1

1250' S of N Line & 75' W of E Line  
NE/4 of Section 10-13-14  
Russell County, Kansas

R.T.D. 3210 1/2

Commenced 8/30/55  
Completed 9/13/55

Casing Record

8 5/8" O 660' w/ 350 sx cnt.  
5 1/2" O 3209' w/ 225 sx cnt.

| Tops                     |      |
|--------------------------|------|
| Cimarron Anhydrite       | 763  |
| Tarkio Sand #1           | 2323 |
| Tarkio Sand #2 (Langdon) | 2337 |
| Tarkio Lime              | 2381 |
| Tarkio Sand #3 (Willard) | 2401 |
| Topoka Lime              | 2654 |
| Heebner Shale            | 2880 |
| Toronto Lime             | 2898 |
| Lansing K.C.             | 2942 |
| Conglomerate             | 3189 |
| Arbuckle                 | 3209 |

----- Figures Indicate Bottom of Formation -----

|                      |          |
|----------------------|----------|
| Shale, Sand & Shells | 300'     |
| Shale & Shells       | 500      |
| Red Bed              | 763      |
| Anhydrite            | 808      |
| Shale & Shells       | 1460     |
| Shale, Lime, Shells  | 1590     |
| Shale & Lime         | 1720     |
| Lime                 | 2005     |
| Shale & Lime         | 2225     |
| Shale                | 2323     |
| Sand                 | 2362     |
| Lime                 | 2385     |
| Shale & Lime         | 2657     |
| Lime                 | 2819     |
| Lime & Shale         | 2906     |
| Lime                 | 3210 1/2 |

STATE OF KANSAS)  
RUSSELL COUNTY ) SS

I hereby certify that the above information is correct to the best  
of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By John R. Drown

Subscribed and sworn to before me this 16th day of September, 1955.

Wm. L. ...  
Notary Public

My Commission Expires 6/17/59

**PLUGGING**  
FILE SEC. 10-13-14  
BOOK PAGE 6 LINE 29

RECEIVED  
COMMISSION  
OCT 17 1955  
REGISTRATION DIVISION  
Wichita, Kansas