

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20185-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 2-20S-33W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: BARNHART Well #: 2-1
County: SCOTT Total Vertical Depth: 2685 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2681	0	WITH 450 SX CMT
SURF	8.625	244		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/22/2016 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: SHANE PELTON Company: HERMAN L LOEB Phone: (618) 943-2227

Proposed Plugging Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.
--

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/22/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150# HULLS & 85 SX CMT TO 2645'. DISPLACE WITH WATER TO 1425'. PRESSURE TO 600#. HOLDING. RAN CBL FROM 1315' TO 20'. TOC BEHIND 4 1/2" CASING IS 243'. PERFORATE 4 HOLES IN 4 1/2" CASING AT 230'. RUN TBG TO 900'. PUMP IN TO PERFS WITH WATER AT 1/2 BPM AT 1000#. NO BLOW OF CIRCULATION UP ANNULUS. CIRCULATE 4 1/2" FULL OF CMT WITH 60 SX CMT. ATTEMPT TO FORCE CMT INTO PERFS AGAIN AT 1100#. COULD NOT. APPARENTLY CMT STRINGERS ABOVE 230'. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS & PUMP 20 SX CMT & PRESSURE TO 500#. HOLDING. TOP OFF 4 1/2" CASING WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2641	2645		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed *Ken Jehlik*
JA (TECHNICIAN)

RECEIVED
AUG 25 2016
KCC DODGE CITY *MP*

Form CP-2/3
OCT 03 2016
no