

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00153-00-00
Spot: NENESWSW Sec/Twnslp/Rge: 7-21S-32W
1290 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DOHRMANN Well #: 1-7
County: FINNEY Total Vertical Depth: 2687 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2685		75 SX
SURF	7.625	339		135 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/19/2016 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: TRACY HOLLIS Company: HERMAN L. LOEB LLC Phone: (719) 340-8985

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/19/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 300# HULLS & 75 SX CMT TO 2680'. DISPLACE WITH WATER TO 1650'.
PRESSURED TO 800#. HOLDING. RUN CBL FROM 1500' TO 0'. FOUND CMT BEHIND
THE 4 1/2" CASING FROM 1480' TO TOC @ 680'. INSUFFICIENT TBG ON LOCATION
TO SPOT A CMT PLUG INSIDE THE 4 1/2" CASING ACROSS THE USABLE WATER
AT 1400' SO WE PERFORATED 4 HOLES AT 1420'. RUN TBG & PACKER TO 1047'.
INJECTION RATE 2 BPM AT 700#. PUMP 50 SX CMT WITH 15 BALL SEALERS IN
THE LAST 10 SX. DISPLACE CMT TO 1000' & PRESSURE TO 1500#. HOLDING.
TOOH WITH TBG & PACKER & PERFORATE 4 HOLES AT 410'. CIRCULATE CMT TO
SURFACE WITH 100 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 7 5/8"
ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2658	2680		
2622	2626		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG 25 2016
KCC DODGE CITY

OCT 03 2016

Form CP-2/3

