

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21592-00-00
Spot: N2N2SWNW Sec/Twnshp/Rge: 31-14S-29W
1500 feet from N Section Line, 660 feet from W Section Line
Lease Name: LUNDGREN TRUST A Well #: 1
County: GOVE Total Vertical Depth: 4385 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4281		195 SX
SURF	8.625	264		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2016 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 2092' w/250 sx cement.
Perforations: 4168' - 4172', 4240' - 4246', 4276' - 4282'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2016 5:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4215' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 3531' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2428' and pumped 75 sx cement. Pulled tubing to 1325' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out and topped off w/25 sx cement. Checked backside and cement was to surface.

GPS: 38.79712 -100.59344

Perfs:

Top	Bot	Thru	Comments
4276	4282		
4240	4246		
4168	4172		

Remarks: BASIC CEMENT TICKET # 14104

Plugged through: TBG

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

cm

AUG 26 2016

SEP 06 2016
CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016

Form CP-2/3