

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24755-00-00
Spot: SESE Sec/Twnshp/Rge: 30-19S-12W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: KOHLER Well #: 12-A
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3450	1792	300 SX
SURF	8.625	314		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2016 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMANN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 1792'. Pulled casing to 1350' and pumped 125 sx cement w/200 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 650' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 110 sx cement and 100 # hulls. Pulled casing and hole stayed full.

GPS: 38.36376 -098.68456

Perfs:

Top	Bot	Thru	Comments
3398	3404		
3372	3378		
3358	3364		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

AUG 29 2016

SEP 06 2016
CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016
Form CP-2/3