

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-29804-00-00
Spot: NWNENE Sec/Twnshp/Rge: 6-32S-16E
5017 feet from S Section Line, 1011 feet from E Section Line
Lease Name: KNIPMEYER Well #: 1
County: MONTGOMERY Total Vertical Depth: 1215 feet

Operator License No.: 33365
Op Name: LAYNE ENERGY OPERATING, LLC
Address: 610 S. 38TH STREET
KANSAS CITY, KS 66106

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1202		142 SX
SURF	7	32		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 07/05/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: PATRICK LOVE Company: _____ Phone: (281) 475-2579

Proposed Plugging Method: Per KCC rules and regulations.

Received
KANSAS CORPORATION COMMISSION
SEP 01 2016
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 07/07/2016 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH to 1180' pump 2 sxs gel and 35 sxs of 60/40 poz w/ 4% gel, pulled up to 550' pump 50 sxs 60/40 poz w/ 4% gel, pull up to 250' and circulate cement to surface, topped off w/ 2 sxs, Dug down 3' and cut off WH and refilled hole,

Perfs:

Top	Bot	Thru	Comments
1180	1181		
1168	1170		
1112	1114		
966	970		

RECEIVED
KCC DIST # 3
AUG 26 2016
CHANUTE, KS

RH

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)

OCT 03 2016 Form CP-2/3
220