

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40236-00-00
Spot: SWNENWSE Sec/Twnshp/Rge: 10-34S-12E
2137 feet from S Section Line, 1900 feet from E Section Line
Lease Name: COUNTY FARM A Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 940 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.875	740		0 SX
SURF	8.25	80		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2016 1:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 900' gelled hole and spotted 20 sack plug. Pulled up to 700' and spotted 20' sack plug. Pulled 1" and perforated casing at 350'. Ran back into 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 160 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
902	938		
RECEIVED KCC DIST # 3 SEP 12 2016 CHANUTE, KS DS			

Remarks: WELL WAS PLUGGED DUE TO PLUGGING AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)

KCC WICHITA

SEP 14 2016

RECEIVED

OCT 03 2016 Form CP-2/3

700