

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-01910-00-00  
Spot: NESEWNNE Sec/Twnshp/Rge: 5-33S-15E  
4502 feet from S Section Line, 1543 feet from E Section Line  
Lease Name: JOY/JONES Well #: 5  
County: MONTGOMERY Total Vertical Depth: 740 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD.	2.875	740		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE  
Date/Time Plugging Completed: 07/08/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 700' gelled hole and spotted 3 sack plug. Pulled up to 500' and spotted 3 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 15 sacks of cement were used to plug this well.

RECEIVED  
KCC DIST # 3  
SEP 13 2016  
CHANUTE, KS


DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

SEP 16 2016

CONSERVATION DIVISION  
WICHITA, KS

OCT 03 2016  
JW

Form CP-2/3