

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-21005-00-00  
Spot: SWSESWSE Sec/Twnshp/Rge: 5-33S-14E  
219 feet from S Section Line, 1889 feet from E Section Line  
Lease Name: SOUTH JANZEN Well #: 2  
County: MONTGOMERY Total Vertical Depth: 1229 feet

Operator License No.: 32255  
Op Name: KANSAS ENERGY COMPANY, L.L.C.  
Address: BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1200		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/03/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P.J. BUCK Company: \_\_\_\_\_ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/04/2016 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 900' and circulated cement to surface. Pulled 1" and topped well off. A total of 80 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1176	1188		

RECEIVED  
KCC DIST # 3  
SEP 13 2016  
CHANUTE, KS  
DS

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed

*Duane A Sims*

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

SEP 16 2016

CONSERVATION DIVISION  
WICHITA, KS

OCT 03 2016

*W*

Form CP-2/3