

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-01561-00-00
Spot: NENENE Sec/Twnshp/Rge: 1-33S-14E
4749 feet from S Section Line, 657 feet from E Section Line
Lease Name: DARBY Well #: I4
County: MONTGOMERY Total Vertical Depth: 1200 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1200		0 SX
SURF	7	20		0 SX

Well Type: EOR UIC Docket No: E24647.1 Date/Time to Plug: 08/01/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/02/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1160' gelled hole and spotted 3 sack plug. Pulled up to 700' and spotted 3 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 15 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1176	1188		

RECEIVED
KCC DIST # 3
SEP 13 2016
CHANUTE, KS
DS


Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Received
KANSAS CORPORATION COMMISSION

Signed



(TECHNICIAN)

SEP 16 2016

CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016

Form CP-2/3

NO
CC UIC