

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-27483-00-00
Spot: NESENENE Sec/Twnshp/Rge: 1-33S-14E
4536 feet from S Section Line, 148 feet from E Section Line
Lease Name: DARBY Well #: 6-B
County: MONTGOMERY Total Vertical Depth: 1200 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 2.875 | 1200 | | 0 SX |
| SURF | 7 | 20 | | 0 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/03/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1180' gelled hole and spotted 3 sack plug. Pulled up to 700' and spotted 3 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 15 sacks of cement were used to plug this well.

Perfs:

| Top | Bot | Thru | Comments |
|--|------|------|----------|
| 1176 | 1188 | | |
| RECEIVED KCC DIST # 3 SEP 13 2016 CHANUTE, KS DS | | | |

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed *Duane A Sims*
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
SEP 16 2016
CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016
no