

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22562-00-01
Spot: W2NWNENW Sec/Twnshp/Rge: 7-33S-2E
330 feet from N Section Line, 1510 feet from W Section Line
Lease Name: AG-NH Well #: 3-7-2
County: SUMNER Total Vertical Depth: 3655 feet

Operator License No.: 35032
Op Name: K3 OIL & GAS OPERATING COMPANY
Address: 24900 PITKIN RD SUITE 305
THE WOODLANDS, TX 77386

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3610		185 SX
SURF	7.78	256		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2016 12:00 AM
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.
Proposal Rcvd. from: JOHN RIGAS Company: _____ Phone: (832) 832-8558

Proposed Plugging Method: set CIBP @3300' w/2 sacks of cement; attempt to pull casing or shoot squeeze holes at 300' circulate cement to surface

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 09/06/2016 3:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP set @3300' capped with 2 sx. Tried to shoot off casing at 2150' with no success, so shot off casing again at 1960' and pulled up 300'. Circulated cement to surface. Plugged out casing and topped off with a 60/40 pos-mix of 123 sx total. Casing stood full. Cut off below surface. Job complete.

Perfs:

Top	Bot	Thru	Comments
3392	3402		

Remarks: WELL PLUGGED DUE TO DENIED TA APPLICATION FROM HIGH FLUID LEVEL.

Plugged through: TBG

District: 02

Signed

Daniel R. Fox
(TECHNICIAN)

OCT 03 2016
NO