

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-20505-00-00
Spot: NENWSW Sec/Twnshp/Rge: 13-20S-10W
1983 feet from S Section Line, 4261 feet from E Section Line
Lease Name: EATINGER Well #: 1
County: RICE Total Vertical Depth: 3369 feet

Operator License No.: 31528
Op Name: MIKE KELSO OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2609		250 SX
SURF	8.625	205		180 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/07/2016 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Per KCC Rules and Regulations.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 09/07/2016 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, pull rods and tubing, CK bottom with swab bar. Sand perfs to 1390' and cap with 5 sxs cement. Cut casing at 1340' and pull 1jt. out. Pump 35 sxs common cement with 3% CC at 1300', pull casing to 900' and let setawhile. Tag cement at 1200" with swab bar. Pumped 35 sxs common cement with 3% CC at 900'. Pulled casing to 400" and circulated cement to surface. Tried to pull casing on out and got stuck at 340'. Topped off both casings.

Perfs:

Top	Bot	Thru	Comments
2299	2302		
1440	1442		

Remarks: TA-N.O.V. LETTER SENT. COPELAND CEMENT #C- 44256.

Plugged through: TBG

District: 02

Signed Duff Klock DISTRICT SUPERVISOR
(TECHNICIAN)

OCT 03 2016 Form CP-2/3

no