

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01469-00-01
Spot: SESWNE Sec/Twnshp/Rge: 25-25S-8E
2310 feet from N Section Line, 1750 feet from E Section Line
Lease Name: JACKSON HEIRS C Well #: 2
County: GREENWOOD Total Vertical Depth: 2482 feet

Operator License No.: 5697
Op Name: JACKSON BROTHERS, L.L.C.
Address: 116 E 3RD ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2482		85 SX
SURF	8.625	84		40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2016 8:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: _____ Phone: (620) 583-5122

Proposed Plugging Method: 1. Cement plug inside 4.5" casing from 2380 to 2320 feet below G.L. 2. Cement plug inside and outside 4.5" casing from 1100 to 1050 feet. 3. Cement plug inside and outside 4.5" casing from 250 feet to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 09/02/2016 12:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

build rock bridge @ 2400' used dump balerr to spot 10 sxs cement on bridge, perfed well @ 1100' & 250', ran tubing to 1100' pumped 25 sxs cement, pulled tubing to 260' pumped 65 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2422	2434		
RECEIVED KCC DIST # 3 SEP 12 2016 CHANUTE, KS MH			

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

SEP 16 2016

CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016

no

Form CP-2/3

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Received 2 September 2016
 Cement or Acid Field Report
 Ticket No. 2917
 Foreman Russell McCoy
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
9-2-2016	1008	JACKSON Heirs. C # 2	25	25S	8E	G.W.	KS	
Customer JACKSON Brothers LLC			Safety Meeting Rm Steve 201		Unit #	Driver	Unit #	Driver
Mailing Address 116 E. 3 RD					102	Russ		
City Eureka					110	zevi		
State KS					145	steve		
Zip Code 67045								

Job Type P.T.A. Hole Depth _____ Slurry Vol. 22 Bbl Tubing 2 3/8
 Casing Depth 2482' Hole Size 7 7/8" Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing 260 to top Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting + Job Procedure 2 Perfs (A) 1100 2 Perf (A) 250

SPOT 25 SKS (A) 1100
 SPOT 65 SKS (A) 260 to SURFACE
 90 SKS TOTAL

Thank you Russell
 McCoy

GOOD CEMENT RETURNS TO SURFACE

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	15	Mileage	3.95	59.25
C-203	90	SKS 60/40 Pozmix	12.75	1147.50
C-206	150 [#]	Gel = 4%	.20	30.00
C-108	3.87	TOW mileage	42. MIL	172.50
C-113	2 1/2	hr 80 Bbl UAC TRUCK	85.00	212.50
C-206	150 [#]	Gel SPACE 1100-260	.20	30.00
Received KANSAS CORPORATION COMMISSION SEP 16 2016 CONSERVATION DIVISION WICHITA, KS				2,461.75
				Less SK 120.00
				Sales Tax 171.12

Authorization Russell J Jackson II Title CO-MANAGER Total 2,452.79 JK

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.