

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19952-00-01
Spot: SESWNE Sec/Twnshp/Rge: 26-25S-8E
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: JACKSON HEIRS Well #: 6
County: GREENWOOD Total Vertical Depth: 2470 feet

Operator License No.: 5697
Op Name: JACKSON BROTHERS, L.L.C.
Address: 116 E 3RD ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2500		0 SX
SURF	8.625	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2016 1:00 PM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: _____ Phone: (620) 583-5122

Proposed Plugging Method: 1. Continuous cement plug inside 4.5" casing from 2430-2345 feet. 2. Shoot 4.5" in two at 1200 feet. 50 foot cement plug (est. 20 sacks) inside rotary hole at 1200-1150 feet. 3. Shoot 4.5" in two at 250 feet. Continuous cement plug inside rotary hole and surface casing from 250 feet to land surface.

Received
KANSAS CORPORATION COMMISSION

Plugging Proposal Received By: MICHAEL HEFFERN
Date/Time Plugging Completed: 08/23/2016 12:00 AM

Witness Type: PARTIAL
KCC Agent: MICHAEL HEFFERN

SEP 01 2016
CONSERVATION DIVISION
WICHITA, KS

Actual Plugging Report:

used dump baler to to spot 15 sxs cement on rock bridge, built bridgr @ 1010' used dump baler , ran tubing to 250' , pumped 50 sxs cement to surface.

Perfs:

Top	Bot	Thru	Comments
2448	2464		
2398	2404		

RECEIVED
KCC DIST # 3
AUG 29 2016
CHANUTE, KS

MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike Hoffmann
(TECHNICIAN)

OCT 03 2016

700

15-673-19952 0001

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **2896**
Foreman Kevin McCoy
Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-23-16	1008	DW JACKSON HEIRS #6	26	25S	8E	Gw	Ks	
Customer <u>JACKSON BROTHERS, LLC</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>116 E. 3rd</u>			102		RICK L.		Received	
City <u>EUREKA</u>			112		STEVE M.		KANSAS CORPORATION COMMISSION	
State <u>Ks</u>			141		DAVE G.		SEP 01 2016	
Zip Code <u>67045</u>							CONSERVATION DIVISION WICHITA, KS	

Job Type P.T.A. Hole Depth _____ Slurry Vol. _____ Tubing _____
 Casing Depth _____ Hole Size 6 1/4" Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other 7" SURFACE CASING
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: Long Drilling Co. Set Bottom Plug & Middle Plug w/ Cable Tool Rig. Cornish wire line shot 2 holes @ 250' in 4 1/2. Rig up to 4 1/2 casing, BREAK CIRCULATION w/ Fresh water. Mixed 50 sks 60/40 Pozmix Cement w/ 2% Gel. Good Cement to SURFACE. 4 1/2 Plugged Solid From 250' to SURFACE inside & out. Job Complete. Rig down.

Built Bridge at 2435' 10SKS Cement
Ripped CASING at 1000 Built Bridge a1010 15SKS Cement

Code	Qty. or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	15	Mileage	3.95	59.25
C 203	50 sks	60/40 Pozmix Cement	12.75	637.50
C 206	85 #	Gel 2%	.20 #	17.00
C 108	2.15 TONS	Ton Mileage	1/2 m/c	172.50
C 113	2 Hrs	80 BBL VAC TRUCK	85.00	170.00
C 224	1500 gals	CITY WATER	10.00/1000	15.00
<u>THANK You</u>			<u>Sub TOTAL</u>	<u>1821.25</u>
			<u>Less 5%</u>	<u>97.89</u>
			<u>7.5% Sales Tax</u>	<u>136.59</u>
			<u>Total</u>	<u>1859.95</u>

Authorization Rossie Jackson II Title CO-MANAGER Total 1859.95

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.