

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22971-00-01
Spot: SESWNW Sec/Twnshp/Rge: 25-31S-10W
2878 feet from S Section Line, 4387 feet from E Section Line
Lease Name: CHAIN RANCH 'A' Well #: 1
County: BARBER Total Vertical Depth: 4854 feet

Operator License No.: 32798
Op Name: HART ENERGIES, LLC
Address: 7122 S SHERIDAN RD STE 2-363
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4854	2635	WITH 235 SX CMT
SURF	8.625	292		WITH 200 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 09/20/2016 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT & 100# HULLS FOR BOTTOM. PLUG AT 680' WITH 10 SX GEL & 50 SX CMT. PLUG AT 325' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: PARTIAL
Date/Time Plugging Completed: 09/20/2016 6:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 150# HULLS & 30 SX CMT. DISPLACED CMT TO 4285'. SHUT IN AT 500#. 1ST PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 335' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. 9/21/16: TOPPED OFF 8 5/8" SURFACE PIPE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4484	4486		
4480	4484		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: Q1

Signed

Steve Pfeifer
51A

(TECHNICIAN)

RECEIVED
SEP 23 2016 *MP*
KCC DODGE CITY

OCT 03 2016

MP Form CP-2/3