

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21033-00-00
Spot: NENWNW Sec/Twship/Rge: 21-34S-28W
4902 feet from S Section Line, 4314 feet from E Section Line
Lease Name: CORDES Well #: B 1-21
County: MEADE Total Vertical Depth: 3290 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 8100 E. 22ND ST. NORTH, BLDG 1500 S
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3145		WITH 2 SX CMT
PROD	4.5	3288	0	WITH 125 SX CMT
SURF	8.625	1539		WITH 465 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2016 10:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Revd. from: DAVE CALLEWAERT Company: EAGLE CREEK CORPORATION Phone: (316) 264-8044

Proposed Plugging Method: SET CIBP @ 3145' WITH 2 SX CMT. PERFORATE AT 1589'. PUMP 50 SX CMT IN & OUT PLUG DOWN CASING. PERFORATE AT 550'. CIRCULATE CMT TO SURFACE INSIDE 4 1/5" X 8 5/8" ANNULUS & THE 4 1/2" CASING.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2016 3:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 3145' WITH 2 SX CMT. PERFORATED AT 1580' & PUMPED 50 SX IN & OUT PLUG. HAD NO CIRCULATION OR BLOW ON BACKSIDE. SHUT DOWN FOR 2 HOURS. RAN WIRELINE DOWN BUT DID NOT TAG CMT. LOADED HOLE & HAD BLOW ON BACKSIDE. PUMPED ANOTHER 50 SX CMT IN & OUT PLUG. HAD GOOD CIRCULATION. SHUT DOWN 1 HOUR TO EQUALIZE & LET CMT SET. PERFORATE AT 550' & CIRCULATED CMT TO SURFACE OF THE 4 1/2" X 8 5/8" ANNULUS & 4 1/2" CASING WITH 150 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3195	3198		

Remarks: USED 60/40 POZMIX 4% GEL 2% CC BY ELITE CEMENTING.

Plugged through: CSG

District: 01

Signed

[Signature] ECAS
(TECHNICIAN)

RECEIVED
AUG 30 2016
KCC DODGE CITY

OCT 03 2016 Form CP-2/3

NO