

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21494-00-00
Spot: S2SWSE Sec/Township/Rge: 34-22S-17W
410 feet from S Section Line, 1980 feet from E Section Line
Lease Name: FRICK Well #: 2-34
County: PAWNEE Total Vertical Depth: 4240 feet

Operator License No.: 34402
Op Name: GARAL, DONNA AND VINCENT INNON
Address: 30-38 48 ST
ASTORIA, NY 11103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4064		WITH 2 SX CMT
PROD	4.5	4238	0	WITH 150 SX CMT
SURF	8.625	814		WITH 335 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/12/2016 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: CIBP @ 4060' WITH 2 SX CMT. PERFORATE AT 1100' & CIRCULATE CMT IN & OUT OF 4 1/2".

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2016 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4064' WITH 2 SX CMT. PERFORATE 4 1/2" CASING AT 1100' & BREAK CIRCULATION. PUMP 525 SX CMT & CIRCULATE CMT TO SURFACE BETWEEN 5 1/2" CASING & 8 5/8" SURFACE CASING. HOLE STAYED FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4110	4116		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: CSG

District: 01

Signed [Signature]
SA (TECHNICIAN)

RECEIVED
AUG 17 2016
KCC DODGE CITY [Signature]

OCT 03 2016
[Signature] Form CP-2/3