

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25668-00-00  
Spot: NWSESESW Sec/Twnshp/Rge: 22-19S-15W  
480 feet from S Section Line, 2100 feet from W Section Line  
Lease Name: DEINES Well #: 1-22  
County: BARTON Total Vertical Depth: 3700 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3699		155 SX
SURF	8.625	889		350 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2016 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F G HOLL COMPANY LLC. DBA Phone: (620) 793-0915

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/22/2016 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 1425'. Pulled casing to 1300' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 3 hulls. Pulled casing to 300'. Circulated cement to surface with 95 sx cement and 100 # hulls. Pulled casing and hole stayed full.

GPS: 38.37792 -098.97025

Perfs:

Top	Bot	Thru	Comments
3644	3650		
3604	3650		

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

SEP 06 2016

CONSERVATION DIVISION  
WICHITA, KS

OCT 03 2016

*no*

Form CP-2/3

AUG 23 2016