

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-21237-00-00  
Spot: NWSWSWSE Sec/Twnshp/Rge: 20-34S-2E  
383 feet from S Section Line, 2386 feet from E Section Line  
Lease Name: ATKINS Well #: 2  
County: SUMNER Total Vertical Depth: 3610 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3114		
PROD	5.5	3599		150 SX
SURF	8.625	242		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2016 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GUS MYERS Company: \_\_\_\_\_ Phone: (918) 244-8063

Proposed Plugging Method: Set CIBP @ 3000' and spot 4 sks cement ; shoot squeeze holes @ 300' ; run 310' 2.375 tbg and cement to surface

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2016 3:00 PM KCC Agent: DAN FOX

**Actual Plugging Report:**

CIBP set @3000' capped with 2sx. Perforated 5 1/2" @ 300', ran tubing in to 310'. Circulated cement to surface. Topped off with cement and returned next week to verify cement stayed to surface. Cut off casing below ground and graded surface. 60/40 pos-mix w/4% gel.  
Consolidated cement ticket #6500000263

**Perfs:**

Top	Bot	Thru	Comments
3209	3215		
3049	3052		

Remarks: WELL PLUGGED AS PART OF DOCKET # 15-442 COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed   
(TECHNICIAN)

OCT 03 2016 Form CP-2/3  
no