

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-20702-00-02
Spot: SWNWNW Sec/Twnshp/Rge: 32-34S-2E
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LESPERANCE Well #: 1
County: SUMNER Total Vertical Depth: 3517 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3475		
PROD	4.5	3516		125 SX
SURF	8.625	266		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2016 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GUS MYERS Company: _____ Phone: (918) 244-8063

Proposed Plugging Method: Set CIBP @ 3350' and spot 4 sks cement; shoot squeeze holes @ 300'; Run 310' 2.375 tbg and circulate cement to surface.

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 07/28/2016 11:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

CIBP set @ 3350' capped with 4sx. Perforated 4 1/2" @ 300'. Ran tubing in to 320'. Circulated 130 sx of cement to surface. Topped off with cement and returned next day to verify cement stayed to surface. Cut off casing below ground and graded surface. 60/40 pos-mix w/ 4% gel.

Top	Bot	Thru	Comments
3502	3508		
3410	3418		

Consolidated cement ticket #6500000238

Remarks: WELL PLUGGED AS PART OF DOCKET #15-442 COMPLIANCE AGREEMENT

Plugged through:

District: 02

Signed _____

Daniel J. King
(TECHNICIAN)

OCT 03 2016

Form CP-2/3

no