

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22446-00-00
Spot: E2NENE Sec/Twnshp/Rge: 16-35S-2E
660 feet from N Section Line, 330 feet from E Section Line
Lease Name: LAWSON Well #: 1-16
County: SUMNER Total Vertical Depth: 3850 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2258		125 SX
SURF	8.625	250		175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/16/2016 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GUS MYERS Company: _____ Phone: (918) 244-8063

Proposed Plugging Method: Set CIBP @ 2075' and spot 4 sks cement ; shoot squeeze holes @ 300' ; Circulate cement to surface

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/18/2016 2:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP set @ 2075' capped with 4sx. Perforated 4 1/2' @ 300', ran tubing in to 310'. Circulated cement to surface. Topped off with cement and returned next week to verify cement stayed to surface. Cut off casing below ground and graded surface. 60/40 pos-mix w/4% gel.

Consolidated cement ticket #6500000264


Perfs:

Top	Bot	Thru	Comments
3050	3060	TBG	
2138	2140		

Remarks: WELL PLUGGED AS PART OF DOCKET #15-442 COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed 
(TECHNICIAN)

OCT 03 2016_{orm} CP-2/3
no