

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-21099-00-00  
Spot: SWNESE Sec/Twnship/Rge: 20-34S-2E  
1986 feet from S Section Line, 445 feet from E Section Line  
Lease Name: ATKINS JOE Well #: 1  
County: SUMNER Total Vertical Depth: 3900 feet

Operator License No.: 32887  
Op Name: ENDEAVOR ENERGY RESOURCES, LP  
Address: 110 N MARIENFELD, STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3450		
PROD	5.5	3577		150 SX
SURF	8.625	242		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2016 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Revd. from: GUS MYERS Company: \_\_\_\_\_ Phone: (918) 244-8063

Proposed Plugging Method: Set CIBP @ 3000' and spot 4 sks cement; shoot squeeze holes @ 300' ; Run 310' 2.375 tbg and cement to surface

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2016 4:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

Perfs:

CIBP set @ 3000' capped with 4sx. Perforated 5 1/2" @ 300', ran tubing in to 310'. Circulated cement to surface. Topped off with cement and returned next week to verify cement stayed to surface. Cut off casing below ground and graded surface. 60/40 pos-mix w/4% gel.

Consolidated cement ticket #6500000262


Top	Bot	Thru	Comments
3513	3523		
3050	3056		

Remarks: WELL PLUGGED AS PART OF DOCKET #15-442 COMPLIANCE AGREEMENT.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

  
(TECHNICIAN)

OCT 03 2016 Form CP-2/3

*no*