

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-20294-00-00  
Spot: SWNWNENW Sec/Twnshp/Rge: 15-34S-12E  
4740 feet from S Section Line, 3717 feet from E Section Line  
Lease Name: WINDERS Well #: 6  
County: CHAUTAUQUA Total Vertical Depth: 946 feet

Operator License No.: 32619  
Op Name: EXCEL OIL & GAS L.L.C.  
Address: PO BOX 68  
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	946		30 SX
SURF	7	250		0 SX

Well Type: EOR UIC Docket No: E18364.1 Date/Time to Plug:  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: P J BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull up to 700' and set 50' plug. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/15/2016 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 940' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 45 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
905	917		

RECEIVED  
KCC DIST # 3  
SEP 20 2016  
CHANUTE, KS  
DS

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

KCC WICHITA

SEP 26 2016

RECEIVED

OCT 03 2016

Form CP-2/3

NO  
CC 412