

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-23558-00-00  
Spot: SENESENW Sec/Twnshp/Rge: 8-24S-16E  
3460 feet from S Section Line, 2690 feet from E Section Line  
Lease Name: J STABLER Well #: 23  
County: WOODSON Total Vertical Depth: 1145 feet

Operator License No.: 3449  
Op Name: COEN ENERGY CORPORATION  
Address: 11217 W 140TH PL  
OVERLAND PARK, KS 66221

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	1145		130 SX
SURF	7	90		30 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: SCOTT OWENS Company: \_\_\_\_\_ Phone: (620) 852-3350

Proposed Plugging Method: Fill production casing with cement.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/07/2016 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.875" casing that was cemented inside 7" casing. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from TD to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 30 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
SEP 21 2016  
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

*[Signature]*  
(TECHNICIAN)

KCC WICHITA  
SEP 26 2016  
RECEIVED

OCT 03 2016

*[Handwritten mark]*

Form CP-2/3