

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22653-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 28-19S-10W
2235 feet from N Section Line, 2035 feet from W Section Line
Lease Name: CEMETERY THOMAS Well #: 1
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 6768
Op Name: CARRIE EXPLORATION & DEVELOPM
Address: 1611 COPPER CREEK CT.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2950		
CIBP		3300		
PROD	5.5	3403		180 SX
SURF	8.875	351		265 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2016 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKES TESTING AND SAL Company: _____ Phone: (620) 938-3943

Proposed Plugging Method: Find free point and pull casing.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/18/2016 9:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ck bottom. Sand upper perms to 2750' and cap with 5 sx's cement. Cut casing at 2200' and pull to 1250' and pump 35 sx's common cement with 3% CC, pull casing to 900' and wait awhile. Run swab bar down and tag cement at 1000'. Pumped 35 sx's common cement at 900', pull casing to 400' and circulate 60-40 Poz, 4% gel to surface. Pull casing on out and top off. Used 230 sx's cement total.

Perfs:

Top	Bot	Thru	Comments
3304	3308		
3303	3306		
3302	3306		
3175	3181		
3148	3152		
3056	3060		

Remarks: PIONEER WIRELINE SET 2950' CIBP, PREVIOUSLY, COPELAND CEMENT TICKET # C-43774.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

OCT 03 2016 Form CP-2/3

No

✓ SK