

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20133-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 14-18S-40W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: WEAVER UNIT Well #: 1
County: GREELEY Total Vertical Depth: 3020 feet

Operator License No.: 34997
Op Name: CASILLAS PETROLEUM CORP
Address: 348 RD DD
SATANTA, KS 67870

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1550		
PROD	4.5	3021	0	WITH 210 SX CMT
SURF	8.625	1247		WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/22/2016 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OPS, LLC
Proposal Revd. from: KENT PENDERGRAFT Company: CASILLAS PETROLEUM Phone: (620) 276-3693

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAGGED FILL UP DUE TO A CASING LEAK AT 2414'. SPOT 25 SX CMT WITH 100# HULLS AT 2392'. NO CIRCULATION. SET CIBP @ 1550'. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 1500'. INJECTION RATE 1 BPM AT 950#. PUMP 30 SX CMT WITH 50# HULLS IN THE LAST 10 SX DOWN THE CASING. DISPLACE TO 1400' @ 500# LEAVING 8 SX CMT INSIDE THE CASING AND 22 SX CMT OUTSIDE THE CASING. NO CIRCULATION. PERFORATE 4 HOLES AT 1265'. INJECTION RATE 2 1/2 BPM AT 300#. CIRCULATE CMT FROM 1265' TO SURFACE WITH 315 SX CMT LEAVING THE CASING AND 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
2917	2964		

Remarks: **COMPLIANCE ISSUE; DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
SEP 29 2016
KCC DODGE CITY

OCT 03 2016
700

Form CP-2/3