

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23154-00-01
Spot: SESWNESE Sec/Twnshp/Rge: 36-8S-17W
1379 feet from S Section Line, 744 feet from E Section Line
Lease Name: HRABE TED Well #: 7
County: ROOKS Total Vertical Depth: 3400 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 WRD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3374		450 SX
SURF	8.625	214		

Well Type: EOR UIC Docket No: E28811.1 Date/Time to Plug: 08/12/2016 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DONALD A. BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 259-4154

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Cemented bottom to surface with 450 sx cement.
Production perforations: 3035' - 3317'.
Tubing stuck in hole. Top of fish 3214'

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2016 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 3198'. Quality Oil Well Cementing pumped 150 sx cement w/300 # hulls. Pulled tubing to 2108' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1303' and pumped 100 sx cement. Cement circulated. Pulled tubing out of hole. Topped off 5 1/2" casing with 10 sx cement. Hooked up to backside with instant pressure.

Remarks: QUALITY OIL WELL CEMENTING TICKET # 1872

Plugged through: TBG

District: 04

Received
KANSAS CORPORATION COMMISSION

Signed Richard Williams
(TECHNICIAN)

AUG 15 2016
SEP 06 2016
CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016

NO
CC UK

CM
Form CP-2/3