

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22003-00-00
Spot: SWSENE Sec/Twnshp/Rge: 19-7S-19W
2310 feet from N Section Line, 990 feet from E Section Line
Lease Name: SCHOELLER Well #: 6
County: ROOKS Total Vertical Depth: 3457 feet

Operator License No.: 32819
Op Name: BAIRD OIL COMPANY LLC
Address: 113 W MAIN PO BOX 428
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3445		240 SX
SURF	8.625	209		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2016 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BRYANT REESE Company: BAIRD OIL CO. LLC Phone: (785) 689-7456

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 500 # hulls and 12 sx gel (100 # sx).
Production perforations: 3328' - 3388' (Lansing KC), 3445' - 3457' (Arbuckle)

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2016 11:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated 2 holes each at 1505' and 950'. Ran tubing to 3289' and pumped 12 sx gel followed by 75 sx cement w/300 # hulls. Pulled tubing to 1520' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 510' and pumped 75 sx cement to circulate cement to surface. Hooked to 5 1/2" casing and pumped 15 sx cement. Shut in pressure 300 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Shut in pressure 200 psi.

GPS: 39.43125N -099.47646W

Perfs:

Top	Bot	Thru	Comments
3382	3388		
3360	3364		
3340	3346		
3328	3331		
3319	3321		

Remarks: GLOBAL CEMENTING TICKET # 2685

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

CM

SEP 06 2016

CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016

Form CP-2/3

AUG 19 2016

no