

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21465-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 26-12S-33W
2190 feet from N Section Line, 2020 feet from W Section Line
Lease Name: SHALLOW RIVER Well #: 1A
County: LOGAN Total Vertical Depth: 4740 feet

Operator License No.: 34917
Op Name: BICKLE ENERGIES LLC
Address: PO BOX 816
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/03/2016 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: DOUG Company: SOUTHWIND DRILLING, INC. Phone: (785) 735-4142

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE
Date/Time Plugging Completed: 09/03/2016 4:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @2600 w/50 sx
2nd plug @1530 w/100 sx
3rd plug @275 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:


Remarks: QUALITY

Plugged through: DP

Received
KANSAS CORPORATION COMMISSION
SEP 19 2016
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____



(TECHNICIAN)

CM

SEP 17 2016

OCT 03 2016

700

Form CP-2/3