

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19581-00-00

Spot: SWNESE

Sec/Twnshp/Rge: 10-24S-12E

1900 feet from S Section Line, 792 feet from E Section Line

Lease Name: MEYERS

Well #: 3

County: GREENWOOD

Total Vertical Depth: 1828 feet

Operator License No.: 33861

Op Name: ALLEN'S SERVICE INC. DBA RUDE CR

Address: PO BOX 145
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1780		
PROD 7		1790		0 SX
SURF 10		685		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/07/2016 12:00 PM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: ALLEN SERVICE INC

Company:

Phone: (620) 678-3836

Proposed Plugging Method: Set bridge plug in bottom, cement with 20 sacks. Perforate 2 holes at 700' feet cement with 20 sacks. Cement from 150 feet to surface on inside and outside of pipe. Set jell bridges between cement.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 09/07/2016 4:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

built rock bridge @ 1800', ran tubing to 1750', pumped 20 sxs cement, pulled pipe to 700', pumped 20 sxs cement, pulled tubing to 250', pumped 103 sxs cement to surface, perfed well @ 700' & 150', gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1790'	1828		

RECEIVED
KCC DIST # 3
SEP 12 2016
CHANUTE, KS
MH

Remarks:

Plugged through: TBG

District: 03

Received
KANSAS CORPORATION COMMISSION

Signed

Michael Heffern
(TECHNICIAN)

SEP 16 2016

CONSERVATION DIVISION
WICHITA, KS

OCT 03 2016

Form CP-2/3

W

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 2918
 Foreman Russell mclay
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
9-7-16	1,043	Myers # 3				G.W.	Ks	
Customer Rude Crude			Safety Meeting RM AB AM Steve		Unit #	Driver	Unit #	Driver
Mailing Address Box 145					102	Russ		
City Hamilton			State KS		110	Alan m		
Zip Code 66853					145	AB		

Job Type P.T.A. Hole Depth _____ Slurry Vol. 37 861 Tubing 2 3/8
 Casing Depth _____ Hole Size Unknown Slurry Wt. 13.5 Drill Pipe _____
 Casing Size & Wt. 7" Cement Left in Casing _____ Water Gal/SK 6.5 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM 4

Remarks: SPOT 20 SKs @ 1750'
SPOT 20 SKs @ 700'
SPOT 103 SKs @ 150' Inside + out of 7"
143 SKs TOTAL

NOTE Good cement Returns to Surface
 Gel SPACER Between Plugs

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-1052	1	Pump Charge	500.00	500.00
C-107	15	Mileage	3.95	59.25
C-203	143	SKs 60/40 Pozmix w/ 4% Gel	12.75	1823.25
C-108	6.1 Ton	Ton Mileage	1/2 m/c	172.50
C-113	1 hr	Bo Bbl VAC Truck	85.00	85.00
Received KANSAS CORPORATION COMMISSION SEP 16 2016 CONSERVATION DIVISION WICHITA, KS				
			Sub TOTAL	2,640.00
			7.5 %	Sales Tax

Authorization by Allen Dannels Title Partner Total _____

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.