

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21469-00-00  
Spot: NENW Sec/Twnshp/Rge: 18-28S-17W  
4650 feet from S Section Line, 3282 feet from E Section Line  
Lease Name: BYRD HARDY Well #: 3  
County: KIOWA Total Vertical Depth: 4910 feet

Operator License No.: 6926  
Op Name: ADVANTAGE RESOURCES, INC.  
Address: 1775 SHERMAN ST STE 1700  
DENVER, CO 80203

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4720		WITH 2 SX CMT
PROD	4.5	4908	2800	WITH 200 SX CMT
SURF	8.625	509		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/14/2016 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 4720' WITH 2 SX CMT. PLUG AT 1230' WITH HULLS & 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/14/2016 1:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

SET CIBP @ 4720' WITH 2 SX CMT. 1ST PLUG AT 1210' WITH 15 SX GEL & 50 SX CMT 3% CC. SHUT DOWN FOR 1 HOUR. TAGGED CMT AT 1160'. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 60' TO SURFACE WITH 40 SX CMT. APPROXIMATELY 10 SX CMT TO PIT.

Top	Bot	Thru	Comments
4772	4794		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
SEP 19 2016  
KCC DODGE CITY

OCT 03 2016

Form CP-2/3