

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21791-00-00
Spot: SWNE Sec/Twnshp/Rge: 33-23S-32W
3427 feet from S Section Line, 1858 feet from E Section Line
Lease Name: NEELEY Well #: 4
County: FINNEY Total Vertical Depth: 4950 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		WITH 2 SX CMT
PC		3181		WITH 770 SX CMT
PROD	5.5	4949	0	WITH 150 SX CMT
SURF	8.625	530		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: SET CIBP @ 4650' WITH 2 SX CMT. PRESSURE CASING TO 700 PSI, IF HOLD SPOT 20 SX CMT AT 1900'. PERFORATE AT 500' WITH CMT TO 0'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2016 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TBG STUCK. CUT TBG AT 3864' & PUMPED 50 SX CMT WITH 150# HULLS. 2ND PLUG AT 1890' WITH 20 SX CMT. SET CIBP @ 1100' WITH 2 SX CMT, TEST CASING TO 600 PSI. HOLDING. PERFORATE AT 500' & PUMP 125 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4734	4743		
4708	4724		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
SEP - 2 2016
KCC DODGE CITY *MD*

Signed

Kenny Sullivan
SA

(TECHNICIAN)

OCT 03 2016

MD Form CP-2/3