

STATE OF KANSAS
STATE CORPORATION COMMISSION

15.167.00006:00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Russell County, Sec. 32 Twp. 15 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Duke & Wood Drilling Company

Lease Name Keil Well No. 1

Office Address Box 194, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed August 13, 1952

Application for plugging filed August 13, 1952

Application for plugging approved August 13, 1952


Plugging commenced August 13, 1952

Plugging completed August 13, 1952

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3432 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240 ft., set bottom plug, 20 sacks of cement dumped on plug. Filled hole with heavy mud to 35 ft., set top plug, dumped 10 sacks of cement on same, filling to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke & Wood Drilling Company

Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Cecil M. Olson (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson

Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1952

R. Dean Cooley
Notary Public.

My commission expires April 29, 1953.

24-2675-S

2-52-20M

PLUGGING
FILE SEC 32 T 15 R 40
BOOK PAGE 37 LINE 38

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1952
CONSERVATION DIVISION
Wichita, Kansas

8-21-52

WELL LOG
Keil #1
SW SW NE of Section 32-15-14W
Russell County, Kansas

Started: August 2, 1952
Completed: August 13, 1952

Elevation 1917 KB
Anhydrite 916 (-1001)
Heebner 3069 (-1152)
Lansing 3130 (-1213)
Conglomerate 3377 (-1460)

0-55	Surface clay and post rock
55-193	Shale, clay and sand
193-252	Shale, clay, sand and limestone
252-400	Shale, clay and red bed streaks
400-916	Sand, clay, iron and red bed
916-951	Anhydrite
951-1320	Shale and shells
1320-1640	Salt, shale and shells
1640-1890	Lime and shale
1890-2165	Lime and shale
2165-2575	Lime and shale
2575-2755	Lime and shale
2755-3060	Lime
3060-3195	Lime
3195-3328	Lime
3328-3377	Lime
3377-3432	Conglomerate
3432	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton, SS

I, Lynn O. Duke of the DUKE & WOOD DRILLING COMPANY being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Partner

Subscribed and sworn to before me this 19th day of August 1952.

Dean T. Looley
Notary Public

CONSERVATION DIVISION
Wichita, KS
My commission expires: April 29, 1953.

PLUGGING
LOG # 32-15-14W
LOG PAGE 37 LINE 31