

STATE OF KANSAS
STATE CORPORATION COMMISSION
1 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-21333-00-00

LEASE NAME Sauer

WELL NUMBER #2

670 Ft. from S Section Line

670 Ft. from ^W Section Line

SEC. 8 TWP. 24S RGE. 10W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 6-10-02

Plugging Completed 6-11-02

RECEIVED
JUN 25 2002

6-25-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC-WICHITA

LEASE OPERATOR RAYMOND OIL COMPANY, INC.

ADDRESS P.O. Box 48788 Wichita, Kansas 67201

PHONE (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Is a plugging proposal was approved on _____ (date)

Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	221'	None
				5-1/2"	3834'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each side. Pumped off bottom with 50 sacks cement and 200# hulls down long-string. 1500# max, 1200# Shut-in. Shot pipe @ 2400', pulled up to 1450', pumped 35 sacks cement, layed 5-1/2" casing down, ran 2" tubing to 900', pumped 35 sacks cement, pulled tubing to 270' and circulated 95 sacks cement to surface. 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raymond Oil Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 24th day of June, 2002

[Signature]
Notary Public

My Commission Expires: _____



OR