

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.C.R. - 82-3-117

API NUMBER 15-155-21433-00-00

LEASE NAME Sauer

WELL NUMBER 1

1975 Ft. from ^N Section Line

1975 Ft. from ^W Section Line

SEC. 8 TWP. 24S RGE. 10W (E) or (W)

COUNTY Reno

Date Well Completed

Plugging Commenced 1-13-03

Plugging Completed 1-15-03

RECEIVED
JAN 22 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Lotus Operating Co., LLC

ADDRESS 914 E. Douglas Wichita, Kansas 67202

PHONE (316) 262-1077 OPERATORS LICENSE NO. 31980

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 3880'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	219'	200'
				5-1/2"	3853'	2410'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s. Set CIBP @3640' with 2 sacks cement on top. Shot pipe @2410'. pulled up to 1450'. pumped 35 sacks cement, pulled up to 1050', pumped 35 sacks cement and 100% hullts; pulled up to 270' and circulated 100 sacks cement, 60/40 pos. 4% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lotus Operating Co., LLC.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filled in the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st. day of January, 20 03

Irene Herzberg
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form CP
Revised 05-

OR