


15-155-01019-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Reno County. Sec. 27 Twp. 24 Rge. 8 (E) (W)
Location as "NE/CNWxSWx" or footage from lines NE NE NE/4
Lease Owner M. B. Armer
Lease Name Ramer Well No. 1
Office Address 710 Petroleum Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed Aug. 13, 19 53
Application for plugging filed Aug. 13, 19 53
Application for plugging approved Aug. 13, 19 53
Plugging commenced Aug. 13, 19 53
Plugging completed Aug. 13, 19 53
Reason for abandonment of well or producing formation dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy Rotary Mud to 250 ft.
Set bottom plug at 250 ft. spotted 15 sacks cement through drill pipe. Filled with mud to 25 ft. and set plug, tied up plug and spotted with 5 sacks cement at the surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature of L. C. Sponenberg]
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 53

My commission expires Feb. 13, 1956.

[Signature of Notary Public]
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 27 T 24 R 8W
BOOK PAGE 122

AUG 19 1953
8-18-53

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

15-155-61019-0000

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY M. B. Armer

SEC. 27 T. 24 R. 8

FARM Ramer

NO. 1

Loc. NE NE NE

TOTAL DEPTH 3800'

COMM. 8/2/53

COMP. 8/14/53


SHOT OR TREATED

CONTRACTOR M. B. Armer

ISSUED

COUNTY Reno County

KANSAS



CASING

20	10	
15	8	260'
12	6	
13	5	

ELEVATION 1645 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay & Sand	75
Red Bed	135
Red Bed & Shale	260
Red Bed & Sand	550
Shale, Shells & Salt	1250
Shale & Lime	1440
Shale & Shells	1635
Broken Lime	1740
Shale, Lime & Shells	1800
Shale & Lime	2000
Shale & Shells	2450
Shale & Lime	2530
Shale	2590
Shale & Shells	2800
Lime	2975
Lime & Shale	3190
Shale	3230
Lime	3660
Lime & Shale	3750
Lime	3800

FORMATION TOPS (R.B. Meas.)

LANSING	3228
MISSISSIPPI	3766

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 18 1953
 CORPORATION DIVISION
 Wichita, Kansas

By

STATE OF KANSAS

COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 17th day of August, 1952.

Notary Public

My Commission expires February 13, 1956.

PLUGGING
 FILE SEC-27 T-24 R-8W
 BOOK PAGE 122 LINE 12