

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County, Sec. 27 Twp. 24S Rge. 8W 1/4 NW  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
NW/4 SW/4 SE/4

Lease Owner National Cooperative Refinery Association  
Lease Name Harriman Well No. 1  
Office Address 1860 Lincoln St., Suite 404, Denver, Colo.  
Character of Well (Completed as Oil, Gas or Dry Hole) D & A


Date Well completed July 22, 1979  
Application for plugging filed July 22, 1979  
Application for plugging approved July 22, 1979  
Plugging commenced July 22, 1979  
Plugging completed July 22, 1979

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3,750'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	195.09'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 500' w/40 sx cement  
Mud to 200' w/25 sx cement  
1/2 sx hulls, plug @ 40' w/10 sx cement  
2 sx cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1979

CONSERVATION DIVISION  
WICHITA, KANSAS

8-3-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. contractor  
Gloria Fawcett (employee of ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 KSB&T Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 1979.

Joyce A. Hagermann  
Notary Public.

My commission expires \_\_\_\_\_



DRILLERS LOG

No. 1 Harriman

CASING RECORD: 8 5/8" @ 205'  
w/200 sx cement

COMPANY: National Cooperative Refinery Asso.  
CONTRACTOR: Red Tiger Drilling Company  
COMMENCED: July 17, 1979  
COMPLETED: July 22, 1979

DESCRIPTION: NW/4 SW/4 SE/4  
Sec. 27-T24S-R8W  
Reno County, Kansas

TOTAL DEPTH: 3750'

ELEVATION: 1,635' GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	35	
Sand	35	95	
Red Bed	95	275	
Shale	275	763	
Anhydrite	763	765	
Shale	765	1128	
Lime & Shale Streaks	1128	1285	
Lime & Shale	1285	1505	
Shale & Lime	1505	1930	
Lime & Shale	1930	2255	
Lime	2255	2895	
Lime & Shale	2895	3355	
Lime	3355	3750	
RTD		3750	

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 3 1979  
OFFICE OF THE SECRETARY  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 24th day of July, 1979.

Joyce A. Hagermann  
Notary Public

