


15.155.20565.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Reno County. Sec. 27 Twp. 24S Rge. 8W E4W
Location as "NE/CNW1SW1" or footage from lines
C-SE; SW SW
Lease Owner Hinkle Oil Company
Lease Name Trembley Well No. 2
Office Address 1010 Union Center Bldg., Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole
Date Well completed December 17, 1978
Application for plugging filed Verbal Application 19__
Application for plugging approved Verbal Approval 19__
Plugging commenced December 17, 1978
Plugging completed December 17, 1978
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes
Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,620'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,620 ft. (rotary total depth) to 270 ft. Set plug at 270 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 270 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 3 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1978
CONSERVATION DIVISION
KANSAS
12-26-78

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sun Oilwell Cementing Co., Inc.
Box 169, Great Bend, Kansas 67530


STATE OF Kansas COUNTY OF Sedgwick ss.
Dean Britting, Agent XXXXXX of owner, XXXXXX of owner or operator

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 19 78

My commission expires July 25, 1982 Elsie Willison - Notary Public.



KANSAS DRILLERS LOG

COMPANY Hinkle Oil Company

SEC. 27 T. 24S R. 8W
LOC. C-SE1 SW SW

FARM Trembley

NO. 2

COUNTY Reno

ROTARY TOTAL DEPTH 3,620'

COMM. December 11, 1978

COMP. December 17, 1978

CONTRACTOR H-30, Inc. (Rig #11)

ISSUED December 17, 1978

CASING

10 3/4"

8 5/8" Set at 247' cemented w/225 sxs cement

ELEVATION 1,616' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	65'
Red Bed	600'
Shale	1,140'
Shale and Lime	1,260'
Lime and Shale	1,410'
Shale and Lime	1,950'
Lime and Shale	2,170'
Shale and Lime	2,590'
Lime	3,620'
Rotary Total Depth	3,620'

I hereby certify the above and foregoing to be
a true and correct log of the above described
well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas

County of Sedgwick

ss:

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 22nd day of
December, 1978.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1978

CONSERVATION DIVISION
Wichita, Kansas