

15-155-20496-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Reno County. Sec. 34 Twp. 24 Rge. 8 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
Approximately C-NW-NW

Lease Owner National Cooperative Refinery Assn.
Lease Name Trembley "A" Well No. 2
Office Address 1860 Lincoln St. Suite 404 Denver, Colo. 80291
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plat

Date Well completed April 18 19 78
Application for plugging filed April 18 19 78
Application for plugging approved April 18 19 78
Plugging commenced April 18 19 78
Plugging completed 6:00 A.M. April 18 19 78
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3942'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug at 500' w/40 sx 50/50 Pozmix, 2 % Gel
Plug at 200' w/25 sx " " "
Plug at 40' W/1/2 sx hulls and 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION

APR 24 1978

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor

STATE OF Kansas COUNTY OF Barton
Wayne Dobbs (employee of owner) or
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs
Wayne Dobbs Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 78

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
My commission expires EXP. 5-20-81

Bessie M. DeWerff
Bessie M. DeWerff Notary Public.

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

NCRA - OPERATOR

TREMBLEY "A" 2
 Approx. C/NW-NW 34-24-8
 RENO COUNTY, KANSAS

ELEV. 1590 KB
 T. D. 3942'

COMMENCED: 4-6-78
 COMPLETED: 4-18-78

Casing

8-5/8" set at 210'

Cement

w/175 sx Common cement, 3% CC

FORMATION

Sand
 Red bed and shale
 Shale & Shells
 Lime & shale
 Shale
 Lime, shale, chert w/sand streaks
 Dolomite

DEPTH

0 - 40
 40 - 500
 500 -1200
 1200-2950
 2950-2954
 2954-3919
 3919-3942

TOPS

Heebner	2950
Lansing	3134
Base K/C	3525
Cong.	3610
Kind.	3636
Viola	3829
Simpson Shale	3836
Simpson Sand	3844
Arb.	3919

RECEIVED
 STATE CORPORATION COMMISSION

APR 24 1978

CONSERVATION DIVISION
 Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton

I, Wayne Dobbs of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Wayne Dobbs
 Wayne Dobbs

Subscribed and sworn to before me on this 20th day of April 1978

BESSIE M. DEWERFF
 STATE NOTARY PUBLIC
 BARTON COUNTY, KANSAS
 MY APPT. EXP. 5-20-81

Bessie M. DeWerff
 Notary Public: Bessie M. DeWerff