


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

XX RENO County. Sec. 34 Twp. 24S Rge. 8 XX W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
W/2 NW/4 NE/4

Lease Owner National Cooperative Refinery Assn.  
Lease Name Barnes Well No. 1  
Office Address 1860 Lincoln Street Denver, Colo. 80295  
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above  
Section Plat

Date Well completed May 12 1978  
Application for plugging filed May 12 1978  
Application for plugging approved May 12 1978  
Plugging commenced 9:30 A.M. May 12 1978  
Plugging completed 10:15 A.M. May 12 1978  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3745'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom plug at 500' w/40 sx 50/50 Pozmix  
Middle plug at 200' w/25 sx " "  
Top plug at 40' w/ 1/2 sx. hulls and 10 sx 50/50 Pozmix  
2 sacks in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

STATE OF Kansas COUNTY OF Barton, ss.  
Wayne Dobbs (employee of owner) or ~~XXXXXX~~  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne Dobbs  
Wayne Dobbs Great Bend, Kansas 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1978

BESSIE M. DEWERFF  
STATE NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
My commission expires 5-20-81

Bessie M. DeWerff  
Bessie M. DeWerff Notary Public.

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR NATIONAL COOPERATIVE REFINERY ASSN. -OPR.

BARNES # 1  
W/2 NE/4 NE/4  
SEC. 34-24S-SW  
RENO COUNTY, KANSAS

T. E. 3745'  
ELEV. 1623' KB

COMMENCED: 5-4-78  
COMPLETED: 5-12-78

Casing

Cement

8-5/8" set at 206'

W/200 ex. Common cement, 3.1 CC

FORMATION

DEPTH

Sand	0 - 70
Shale & Shells	70 - 1200
Lime & Shale	1200 - 2980
Shale	2980 - 2984
Lime & Shale	2984 - 3745

TUBS

Heeb.	2980
Kansas City	3166
Dase K/C	3563
6ong.	3676

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 17 1978  
CONSULTING DIVISION  
Wichita, Kansas

AFFIDAVIT

State of Kansas County of Barton

I, Wayne Hobbs of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Wayne Hobbs  
Wayne Hobbs

Subscribed and sworn to on this 15th day of May 1978

My Commission BESSIE M. DEWERFF  
STATE NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY ABILITY EXP. 5-20-81

Bessie M. Dewerff  
Notary Public: Bessie M. Dewerff