


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Reno County, Sec. 34 Twp. 24 Rge. 8 NE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
870' FWL & 870' FSL of NW/4

Lease Owner NATIONAL COOPERATIVE REFINERY ASSN.
Lease Name TREMBLEY Well No. A-3

Office Address 404 Lincoln Tower Bldg. Denver, Colo
Character of Well (Completed as Oil, Gas or Dry Hole) 80295
dry hole

Date Well completed Feb. 27 1979
Application for plugging filed Feb. 27 1979
Application for plugging approved Feb. 27 1979
Plugging commenced 4:30 P.M. Feb. 27 1979
Plugging completed 5:30 P.M. Feb. 27 1979
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3510'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

500' W/40 sx 50/50 Pozmix, 2% Gel
220' W/25 sx " " " "
Bridge & Plug at 40' W/10 sx. 50/50 Pozmix, 2% Gel.
25 sx in rat hole

3-8-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION
MAILED 6 13/79

STATE OF Kansas COUNTY OF Barton
Don Popp (employee of owner) of

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Don Popp
Hoisington, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 1979

Bessie M. DeWerff
Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. DRILLING COMPANY - CONTRACTOR

NATIONAL COOPERATIVE REFINERY - OPERATOR

TREMBLEY A-3
NW/4 34-24S-8W
RENO COUNTY, KANSAS

ELEV. 1588 KB
T.D. 3510'

COMMENCED: 2-20-79
COMPLETED: 2-27-79

CASING:

8-5/8" set at 230'

CEMENT:

W/200 sx. Common Cement, 3% CC

FORMATION

DEPTH

Shale & shells	0 - 230
Shale	230 -1080
Anhy.	1080-1120
Shale & Shells	1120-1320
Shale W/Lime	1320-2525
Lime & Shale	2525-3210
Lime	3210-3510
R.T.D.	3510

TOPS

Heeb.	2954
Lansing	3142
Stark Shale	3421
Hush Puckney	3457
Hertha Pay	3470-3472
DST # 1	3453-3487

AFFIDAVIT

State of Kansas County of Barton

I, Don Popp of the L. D. Drilling Company

being first duly sworn on oath, State: That I have knowledge of the facts statements and matters herein contained and that the same are true and correct.

Don Popp
Don Popp

Subscribed and sworn to before me on this 28th day of February 1979

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81

RECEIVED
STATE CORPORATION COMMISSION
MAR - 8 1979
CONSERVATION DIVISION
Wichita, Kansas