



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Gopher Oil & Gas Company

Complete Address: 5140 Valentine Road, Wichita, Kansas

Lease Name: Reed Well No. # 1

Location: C S/2 SE NW Sec. 26 Twp. 24 Rge. 12 (E) (W) W

County Stafford Total Depth 4117 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

202' of 8 5/8" surface pipe, cemented with 135 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent